


IF IN DOUBT ASK



Do not scale  
All dimensions in millimetres  
Do not manually alter CAD drawings



No.	Description	Qty	Drawing Number
1	Pig nose Fixing nut	2	LBSL 260/07/007
2	Nylon post washer	4	LBSL 260/07/006
3	Timetable Fixing Stud	2	LBSL 260/07/018
4	Single Solar Timetable Spine	1	LBSL 260/14/040
5	Door Tab	2	LBSL 260/14/023
6	M4 x 10 long s/s Hexagon socket countersunk head machine screws	4	
7	Hinge Block Set LH	1	LBSL 260/14/024
8	M4 x 10 long s/s Hexagon socket countersunk head machine screws	6	
9	Timetable Door	1	LBSL 260/06/015
10	Timetable Glazing	1	LBSL 260/06/016
11	M5 x 19 long s/s tamperproof, Hexagon socket button head machine screws	2	
12	Glazing Extrusion	2	LBSL 260/06/043
13	Upper Box Casting	1	LBSL 260/14/022
14	M5 x 10 long s/s Hexagon socket countersunk head machine screws	2	
15	Lower Box Casting & Button Asy	1	CTC 42261 [See Note 1]
16	M5 x 10 long s/s Hexagon socket countersunk head machine screws	2	
17	Illuminated Tray Assembly	1	CTC 42261 [See note 1]
18	Illuminator Tray	1	LBSL 260/14/055 [See note 2]
19	Battery Pack	1	CTC 42261 [See note 1]
20	Energy Management System [Single]	1	CTC 42262 [See note 3]
21	M4 x 10 long s/s Hexagon socket countersunk head machine screws	2	
22	Velco strip - 20 x 50mm	1 pair	
23	Wire Tie	4	
24	Top Hat Fitting	2	LBSL 260/14/27

NOTES

- 1 Items 15, 17 and 19 form Part No. CTC 42261 supplied by Carmanah Technologies Corp.  
2 Item 18 is fully bonded into item 17 forming a waterproof unit using clear Sikoflex PU adhesive  
3 Item 20 Part No CTC 42262 supplied by Carmanah Technologies Corp.  
4 Items 15, 17, 19 and 20 are as supplied by Carmanah Technologies Corp, similar and approved equivalent items may be used and must comply with LBSL document::  
LBSL Solar Powered Illuminated Bus Stop Specification 30 March 2005



B	10.05.07	New Border
A	28.10.02	FIRST ISSUE
Date		Revision

**London Bus Services Limited**  
Infrastructure Development  
172 Buckingham Palace Road  
London SW1W 9TN  
Telephone 020 7918 4939  
Fax 020 7918 3567

© copyright TfL Original design for LBSL by  
JEDCO Product Designers and Engineering

**METAL BUS STOP  
STANDARD DRAWING**  
Title  
MKII TIMETABLE DISPLAY  
SOLAR SINGLE TIMETABLE  
ASSEMBLY

CALMS code	
© copyright TfL	Drawn on behalf of LBSL by Trueform Engineering Ltd.
Drawn K.N.B.	Checked J.M.
Scale 1:10	Date 28.10.02
Drawing no. LBSL260/14/070	Rev B