


IF IN DOUBT ASK



Do not scale
All dimensions in millimetres
Do not manually alter CAD drawings



No.	Description	Qty	Drawing Number
1	Pig nose Fixing nut	2	LBSL 260/07/007
2	Nylon post washer	4	LBSL 260/07/006
3	Timetable Fixing Stud	2	LBSL 260/07/018
4	Double Solar Timetable Spine	1	LBSL 260/14/060
5	Door Tab	6	LBSL 260/14/023
6	M4 x 10 long s/s Hexagon socket countersunk head machine screws	12	
7	Hinge Block Set RH	1	LBSL 260/14/016
8	M4 x 10 long s/s Hexagon socket countersunk head machine screws	18	
9	Timetable Door	3	LBSL 260/06/015
10	Timetable Glazing	3	LBSL 260/06/016
11	M5 x 19 long s/s tamperproof, Hexagon socket button head machine screws	6	
12	Glazing Extrusion	6	LBSL 260/06/043
13	Upper Box Casting	3	LBSL 260/14/022
14	M5 x 10 long s/s Hexagon socket countersunk head machine screws	6	
15	Lower Box Casting & Button Asy	3	CTC 42261 [See Note 1]
16	M5 x 10 long s/s Hexagon socket countersunk head machine screws	6	
17	Illuminated Tray Assembly	3	CTC 42261 [See note 1]
18	Illuminator Tray	3	LBSL 260/14/055 [See note 2]
19	Battery Pack	3	CTC 42261 [See note 1]
20	Energy Management System [Triple]	1	CTC 42264 [See note 3]
21	M4 x 10 long s/s Hexagon socket countersunk head machine screws	6	
22	Velco strip - 20 x 50mm	1 pair	
23	Wire Tie	12	
24	Hinge Block Set LH	2	LBSL 260/14/024
25	Top Hat Fitting	6	LBSL 260/14/027

NOTES

- 1 Items 15, 17 and 19 form Part No. CTC 42261 supplied by Carmanah Technologies Corp.
2 Item 18 is fully bonded into item 17 forming a waterproof unit using clear Sikoflex PU adhesive
3 Item 20 Part No CTC 42264 supplied by Carmanah Technologies Corp.
4 Items 15, 17, 19 and 20 are as supplied by Carmanah Technologies Corp, similar and approved equivalent items may be used and must comply with LBSL document:: LBSL Solar Powered Illuminated Bus Stop Specification 30 March 2005



B	10.05.07	New Border
A	28.10.02	FIRST ISSUE
Date		Revision

London Bus Services Limited
Infrastructure Development
172 Buckingham Palace Road
London SW1W 9TN
Telephone 020 7918 4939
Fax 020 7918 3567

© copyright TfL Original design for LBSL by JEDCO Product Designers and Engineering

METAL BUS STOP STANDARD DRAWING

Title
MKII TIMETABLE DISPLAY
SOLAR TRIPLE TIMETABLE
ASSEMBLY

CALMS code SEE ANNOTATION

© copyright TfL Drawn on behalf of LBSL by Trueform Engineering Ltd.

Drawn K.N.B. Checked J.M.

Scale 1:10 Date 28.10.02

Drawing no. LBSL260/14/072 Rev B