



IF IN DOUBT ASK

Do not scale
All dimensions in millimetres
Do not manually alter CAD drawings

No.	Description	Qty	Drawing Number
1	Pig nose Fixing nut	2	LBSL 260/07/007
2	Nylon post washer	4	LBSL 260/07/006
3	Timetable Fixing Stud	2	LBSL 260/07/018
4	Double Solar Timetable Spine	1	LBSL 260/14/050
5	Door Tab	4	LBSL 260/14/023
6	M4 x 10 long s/s Hexagon socket countersunk head machine screws	8	
7	Hinge Block Set RH	1	LBSL 260/14/016
8	M4 x 10 long s/s Hexagon socket countersunk head machine screws	12	
9	Timetable Door	2	LBSL 260/06/015
10	Timetable Glazing	2	LBSL 260/06/016
11	M5 x 19 long s/s tamperproof, Hexagon socket button head machine screws	4	
12	Glazing Extrusion	4	LBSL 260/06/043
13	Upper Box Casting	2	LBSL 260/14/022
14	M5 x 10 long s/s Hexagon socket countersunk head machine screws	4	
15	Lower Box Casting & Button Asy	2	CTC 42261 [See Note 1]
16	M5 x 10 long s/s Hexagon socket countersunk head machine screws	4	
17	Illuminated Tray Assembly	2	CTC 42261 [See note 1]
18	Illuminator Tray	1	LBSL 260/14/055 [See note 2]
19	Battery Pack	2	CTC 42261 [See note 1]
20	Energy Management System [Double]	1	CTC 42263 [See note 3]
21	M4 x 10 long s/s Hexagon socket countersunk head machine screws	2	
22	Velco strip - 20 x 50mm	1 pairs	
23	Wire Tie	8	
24	Hinge Block Set LH	1	LBSL 260/14/024
25	Top Hat Fitting	4	LBSL 260/14/027

NOTES

- 1 Items 15, 17 and 19 form Part No. CTC 42261 supplied by Carmanah Technologies Corp.
2 Item 18 is fully bonded into item 17 forming a waterproof unit using clear Sikoflex PU adhesive
3 Item 20 Part No CTC 42263 supplied by Carmanah Technologies Corp.
4 Items 15, 17, 19 and 20 are as supplied by Carmanah Technologies Corp, similar and approved equivalent items may be used and must comply with LBSL document::
LBSL Solar Powered Illuminated Bus Stop Specification 30 March 2005



B	10.05.07	New Border
A	28.10.02	FIRST ISSUE
	Date	Revision

London Bus Services Limited

Infrastructure Development
172 Buckingham Palace Road
London SW1W 9TN
Telephone 020 7918 4939
Fax 020 7918 3567

© copyright TfL Original design for LBSL by JEDCO Product Designers and Engineering

METAL BUS STOP STANDARD DRAWING

Title
MKII TIMETABLE DISPLAY
SOLAR DOUBLE TIMETABLE
ASSEMBLY

CALMS code

© copyright TfL Drawn on behalf of LBSL by Trueform Engineering Ltd.

Drawn K.N.B. Checked J.M.

Scale 1:10 Date 28.10.02

Drawing no. LBSL 260/14/071 Rev B