



METHOD OF CONTROL


Existing



Proposed



KEY



NOTES

- Design based on topographical survey supplied by 40
- Seven undertaken in February 2015
- All designs to be in accordance with TLE and appropriate
- Highway Authority Streetworks guidance
- All signs and signage to be assessed at detailed design stage
- Traffic Signs Regulations and General Directions (TSRGD)
- All dimensions in metres, unless otherwise stated
- All signs to be mounted on existing lighting columns (sign posts where possible (subject to structural assessment))
- Signs on footway to be mounted at a height to ensure a minimum vertical clearance of 2.2m to bottom of sign
- where cycling is permitted on the footway, elsewhere to 2.1m
- All signs to have a minimum horizontal clearance of 450mm from base of kerbed kerb or 250mm from cycle only lane
- All signs to be mounted at a height to ensure a minimum vertical clearance of 2.2m to bottom of sign
- where cycling is permitted on the footway, elsewhere to 2.1m
- All existing signs & lines to be retained unless otherwise stated
- Critical dimensions to be checked at detailed design stage
- Signage to be assessed at detailed design stage
- Proposed traffic signal positions are indicative only and are subject to detailed signal design
- Assess camberway condition at detailed design stage
- Reinstate existing road markings adjacent to kerb and carriageway works
- Changes to drainage are indicative only and are subject to detailed design
- All gullies in cycle track / lane to be converted to cycle heavy
- Statutory Undertakers equipment impeded by the works are to be removed or relocated. Appropriate checks should be made at Detailed Design

FOR INTERNAL USE ONLY.

DESIGN SUBJECT TO CHANGE.

NOT FOR CONSTRUCTION



Transport for London
Road Space Management
Outcomes Design Engineering

Palmer
191 Redcliffe Road
SE1 1NU

schema LB LAMBETH
E&C TO CRYSTAL PALACE QUIETWAY
ROSENDALE ROAD - THURLOW PARK ROAD
OPTION 3

FEASIBILITY DESIGN

date	scale	dm	chk	app
MAY15	1:200 @ A1	TG	MA	-
Draw No	ODE/TC/010.300627-FD-03			
Sheet 1 of 1	0			